

## GENERAL SUMMARY

Prepared for:

Project ID:

Scope:

Fire Alarm

No. Of Floors:

Date:



BUILDING GSF

Sub-Basement (SF)

Basement (SF)

1st Floor (SF)

2nd Floor (SF)



DIVISION NO.	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST
1000	General Requirments	\$ -	\$ -
2000	Demolition	\$ -	\$ -
28000	Fire Alarm	\$ -	\$ -
<b>TOTAL TRADE COST</b>		<b>\$ -</b>	<b>\$ -</b>
<b>OVERHEAD AND PROFIT</b>		15%	\$ -
INSURANCE		0%	\$ -
CONTINGENCY		0%	\$ -
TAX		0%	\$ -
<b>TOTAL TRADE COST</b>		<b>\$ -</b>	<b>\$ -</b>

**BREAKDOWN OF ITEMS**

Prepared for:

Project ID:

Scope: **Fire Alarm**



Date:

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
<b>GENERAL REQUIREMENTS</b>										
1	Permits	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
2	Supervision and Coordination	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
3	Submittals and Shop drawings	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
4	Final Cleaning	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
5	Mobilization Costs	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
6	Temporary Control & Facilities	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
7	Scaffolding	SF	0	0%	0	\$ -	\$ -	\$ -	\$ -	
<b>SUBTOTAL \$</b>									<b>-</b>	
<b>DEMOLITION</b>										
8	Existing Horn/Strobe To Be Removed	EA	22	0%	22	\$ -	\$ -	\$ -	\$ -	
9	Existing Horn To Be Removed	EA	15	0%	15	\$ -	\$ -	\$ -	\$ -	
10	Existing Fire Alarm Manual Pull Station To Be Removed	EA	8	0%	8	\$ -	\$ -	\$ -	\$ -	
11	Existing FACP To Be Relocated	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
12	Existing FAAP To Be Relocated	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
13	Existing Fire Alarm Manual Pull Station To Be Relocated	EA	6	0%	6	\$ -	\$ -	\$ -	\$ -	
<b>SUBTOTAL \$</b>									<b>-</b>	
<b>FIRE ALARM</b>										
	<b>Conduit</b>									
14	3/4" EMT Conduit	LF	1316	10%	1448	\$ -	\$ -	\$ -	\$ -	
	<b>Conductor</b>									
15	#16 CU THHN/THWN	LF	1711	10%	1882	\$ -	\$ -	\$ -	\$ -	
16	#14 CU THHN/THWN	LF	922	10%	1014	\$ -	\$ -	\$ -	\$ -	
	<b>Device</b>									
17	Fire Alarm Annunciator Panel	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
18	Fire Alarm Control Panel	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
19	Horn/Strobe	EA	9	0%	9	\$ -	\$ -	\$ -	\$ -	
20	Pull Station	EA	7	0%	7	\$ -	\$ -	\$ -	\$ -	
21	Smoke Detector	EA	39	0%	39	\$ -	\$ -	\$ -	\$ -	
22	Tamper Switch	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
23	Flow Switch	EA	1	0%	1	\$ -	\$ -	\$ -	\$ -	
	<b>Miscellaneous</b>									
24	Junction Box	EA	3	0%	3	\$ -	\$ -	\$ -	\$ -	
25	Pull Box	EA	5	0%	5	\$ -	\$ -	\$ -	\$ -	
	<b>Fire Stopping</b>									
26	Caulking Sealant	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	
<b>SUBTOTAL \$</b>									<b>-</b>	
							<b>PROJECTED COST</b>			
							0.15	0.15	15%	\$0
<b>OVERHEAD AND PROFIT</b>										
<b>INSURANCE</b>							0	0	0%	\$0
<b>CONTINGENCY</b>							0	0	0%	\$0
<b>TAX</b>							0	0	0%	\$0
<b>SUGGESTED BID</b>									<b>\$0</b>	

**Note:**

- Please verify the equipment's and their prices with owner.
- For tree plantation average prices are use. Please verify according to tree type.
- Online sources are used for pricing.
- Prices can vary depending upon field conditions.